

OSHA[®] GUIDELINES

PROVIDED BY *Thread Source, Inc.*

- Part Number: 1926
 - Part Title: Safety and Health Regulations for Construction
 - Subpart: R
 - Subpart Title: Steel Erection
 - Standard Number: [1926.757](#)
 - Title: Open web steel joists.
 - GPO Source: [e-CFR](#)
-

1926.757(a)

General.

[1926.757\(a\)\(1\)](#)

Except as provided in paragraph (a)(2) of this section, where steel joists are used and columns are not framed in at least two directions with solid web structural steel members, a steel joist shall be field-bolted at the column to provide lateral stability to the column during erection. For the installation of this joist:

1926.757(a)(1)(i)

A vertical stabilizer plate shall be provided on each column for steel joists. The plate shall be a minimum of 6 inch by 6 inch (152 mm by 152 mm) and shall extend at least 3 inches (76 mm) below the bottom chord of the joist with a ^{13/16} inch (21 mm) hole to provide an attachment point for guying or plumbing cables.

1926.757(a)(1)(ii)

The bottom chords of steel joists at columns shall be stabilized to prevent rotation during erection.

1926.757(a)(1)(iii)

Hoisting cables shall not be released until the seat at each end of the steel joist is field-bolted, and each end of the bottom chord is restrained by the column stabilizer plate.

1926.757(a)(2)

Where constructibility does not allow a steel joist to be installed at the column:

1926.757(a)(2)(i)

an alternate means of stabilizing joists shall be installed on both sides near the column and shall:

..1926.757(a)(2)(i)(A)

1926.757(a)(2)(i)(A)

provide stability equivalent to paragraph (a)(1) of this section;

1926.757(a)(2)(i)(B)

be designed by a qualified person;

1926.757(a)(2)(i)(C)

be shop installed; and

OSHA[®] GUIDELINES

PROVIDED BY *Thread Source, Inc.*

1926.757(a)(2)(i)(D)

be included in the erection drawings.

1926.757(a)(2)(ii)

hoisting cables shall not be released until the seat at each end of the steel joist is field-bolted and the joist is stabilized.

1926.757(a)(3)

Where steel joists at or near columns span 60 feet (18.3 m) or less, the joist shall be designed with sufficient strength to allow one employee to release the hoisting cable without the need for erection bridging.

1926.757(a)(4)

Where steel joists at or near columns span more than 60 feet (18.3 m), the joists shall be set in tandem with all bridging installed unless an alternative method of erection, which provides equivalent stability to the steel joist, is designed by a qualified person and is included in the site-specific erection plan.

1926.757(a)(5)

A steel joist or steel joist girder shall not be placed on any support structure unless such structure is stabilized.

..1926.757(a)(6)

1926.757(a)(6)

When steel joist(s) are landed on a structure, they shall be secured to prevent unintentional displacement prior to installation.

1926.757(a)(7)

No modification that affects the strength of a steel joist or steel joist girder shall be made without the approval of the project structural engineer of record.

1926.757(a)(8)

Field-bolted joists.

1926.757(a)(8)(i)

Except for steel joists that have been pre-assembled into panels, connections of individual steel joists to steel structures in bays of 40 feet (12.2 m) or more shall be fabricated to allow for field bolting during erection.

1926.757(a)(8)(ii)

These connections shall be field-bolted unless constructibility does not allow.

1926.757(a)(9)

Steel joists and steel joist girders shall not be used as anchorage points for a fall arrest system unless written approval to do so is obtained from a qualified person.

1926.757(a)(10)

OSHA[®] GUIDELINES

PROVIDED BY *Thread Source, Inc.*

A bridging terminus point shall be established before bridging is installed. (See Appendix C to this subpart.)

1926.757(b)

Attachment of steel joists and steel joist girders.

..1926.757(b)(1)

1926.757(b)(1)

Each end of "K" series steel joists shall be attached to the support structure with a minimum of two ¹/₈-inch (3 mm) fillet welds 1 inch (25 mm) long or with two ¹/₂-inch (13 mm) bolts, or the equivalent.

1926.757(b)(2)

Each end of "LH" and "DLH" series steel joists and steel joist girders shall be attached to the support structure with a minimum of two ¹/₄-inch (6 mm) fillet welds 2 inches (51 mm) long, or with two ³/₄-inch (19 mm) bolts, or the equivalent.

1926.757(b)(3)

Except as provided in paragraph (b)(4) of this section, each steel joist shall be attached to the support structure, at least at one end on both sides of the seat, immediately upon placement in the final erection position and before additional joists are placed.

1926.757(b)(4)

Panels that have been pre-assembled from steel joists with bridging shall be attached to the structure at each corner before the hoisting cables are released.

1926.757(c)

Erection of steel joists.

1926.757(c)(1)

Both sides of the seat of one end of each steel joist that requires bridging under Tables A and B shall be attached to the support structure before hoisting cables are released.

1926.757(c)(2)

For joists over 60 feet, both ends of the joist shall be attached as specified in paragraph (b) of this section and the provisions of paragraph (d) of this section met before the hoisting cables are released.

1926.757(c)(3)

On steel joists that do not require erection bridging under Tables A and B, only one employee shall be allowed on the joist until all bridging is installed and anchored.

Table A -- Erection Bridging for Short Span Joists

Joist	Span
8L1	NM

OSHA[®] GUIDELINES

PROVIDED BY *Thread Source, Inc.*

10K1	NM
12K1	23-0
12K3	NM
12K5	NM
14K1	27-0
14K3	NM
14K4	NM
14K6	NM
16K2	29-0
16K3	30-0
16K4	32-0
16K5	32-0
16K6	NM
16K7	NM
16K9	NM
18K3	31-0
18K4	32-0
18K5	33-0
18K6	35-0
18K7	NM
18K9	NM
18K10	NM
20K3	32-0
20K4	34-0
20K5	34-0
20K6	36-0
20K7	39-0
20K9	39-0
20K10	NM
22K4	34-0
22K5	35-0
22K6	36-0
22K7	40-0
22K9	40-0
22K10	40-0
22K11	40-0
24K4	36-0

OSHA[®] GUIDELINES

PROVIDED BY *Thread Source, Inc.*

24K5	38-0
24K6	39-0
24K7	43-0
24K8	43-0
24K9	44-0
24K10	NM
24K12	NM
26K5	38-0
26K6	39-0
26K7	43-0
26K8	44-0
26K9	45-0
26K10	49-0
26K12	NM
28K6	40-0
28K7	43-0
28K8	44-0
28K9	45-0
28K10	49-0
28K12	53-0
30K7	44-0
30K8	45-0
30K9	45-0
30K10	50-0
30K11	52-0
30K12	54-0
10KCS1	NM
10KCS2	NM
10KCS3	NM
12KCS1	NM
12KCS2	NM
12KCS3	NM
14KCS1	NM
14KCS2	NM
14KCS3	NM
16KCS2	NM
16KCS3	NM

OSHA[®] GUIDELINES

PROVIDED BY *Thread Source, Inc.*

16KCS4	NM
16KCS5	NM
18KCS2	35-0
18KCS3	NM
18KCS4	NM
18KCS5	NM
20KCS2	36-0
20KCS3	39-0
20KCS4	NM
20KCS5	NM
22KCS2	36-0
22KCS3	40-0
22KCS4	NM
22KCS5	NM
24KCS2	39-0
24KCS3	44-0
24KCS4	NM
24KCS5	NM
26KCS2	39-0
26KCS3	44-0
26KCS4	NM
26KCS5	NM
28KCS2	40-0
28KCS3	45-0
28KCS4	53-0
28KCS5	53-0
30KCS3	45-0
30KCS4	54-0
30KCS5	54-0

NM= diagonal bolted bridging not mandatory for joists under 40 feet

Table B -- Erection Bridging for Long Span Joists

Joist	Span
18LH02	33-0
18LH03	NM
18LH04	NM

OSHA[®] GUIDELINES

PROVIDED BY *Thread Source, Inc.*

18LH05	NM
18LH06	NM
18LH07	NM
18LH08	NM
18LH09	NM
20LH02	33-0
20LH03	38-0
20LH04	NM
20LH05	NM
20LH06	NM
20LH07	NM
20LH08	NM
20LH09	NM
20LH10	NM
24LH03	35-0
24LH04	39-0
24LH05	40-0
24LH06	45-0
24LH07	NM
24LH08	NM
24LH09	NM
24LH10	NM
24LH11	NM
28LH05	42-0
28LH06	46-0
28LH07	NM
28LH08	NM
28LH09	NM
28LH10	NM
28LH11	NM
28LH12	NM
28LH13	NM
32LH06	47-0 through 60-0
32LH07	47-0 through 60-0
32LH08	55-0 through 60-0
32LH09	NM through 60-0
32LH10	NM through 60-0

OSHA[®] GUIDELINES

PROVIDED BY *Thread Source, Inc.*

32LH11	NM through 60-0
32LH12	NM through 60-0
32LH13	NM through 60-0
32LH14	NM through 60-0
32LH15	NM through 60-0
36LH07	47-0 through 60-0
36LH08	47-0 through 60-0
36LH09	57-0 through 60-0
36LH10	NM through 60-0
36LH11	NM through 60-0
36LH12	NM through 60-0
36LH13	NM through 60-0
36LH14	NM through 60-0
36LH15	NM through 60-0

NM = diagonal bolted bridging not mandatory for joists under 40 feet.

..1926.757(c)(4)

1926.757(c)(4)

Employees shall not be allowed on steel joists where the span of the steel joist is equal to or greater than the span shown in Tables A and B except in accordance with § 1926.757(d).

1926.757(c)(5)

When permanent bridging terminus points cannot be used during erection, additional temporary bridging terminus points are required to provide stability. (See appendix C of this subpart.)

1926.757(d)

Erection bridging.

1926.757(d)(1)

Where the span of the steel joist is equal to or greater than the span shown in Tables A and B, the following shall apply:

1926.757(d)(1)(i)

A row of bolted diagonal erection bridging shall be installed near the midspan of the steel joist;

1926.757(d)(1)(ii)

Hoisting cables shall not be released until this bolted diagonal erection bridging is installed and anchored; and

1926.757(d)(1)(iii)

No more than one employee shall be allowed on these spans until all other bridging is installed and anchored.

OSHA[®] GUIDELINES

PROVIDED BY *Thread Source, Inc.*

1926.757(d)(2)

Where the span of the steel joist is over 60 feet (18.3 m) through 100 feet (30.5 m), the following shall apply:

1926.757(d)(2)(i)

All rows of bridging shall be bolted diagonal bridging;

1926.757(d)(2)(ii)

Two rows of bolted diagonal erection bridging shall be installed near the third points of the steel joist;

1926.757(d)(2)(iii)

Hoisting cables shall not be released until this bolted diagonal erection bridging is installed and anchored; and

1926.757(d)(2)(iv)

No more than two employees shall be allowed on these spans until all other bridging is installed and anchored.

..1926.757(d)(3)

1926.757(d)(3)

Where the span of the steel joist is over 100 feet (30.5 m) through 144 feet (43.9 m), the following shall apply:

1926.757(d)(3)(i)

All rows of bridging shall be bolted diagonal bridging;

1926.757(d)(3)(ii)

Hoisting cables shall not be released until all bridging is installed and anchored; and

1926.757(d)(3)(iii)

No more than two employees shall be allowed on these spans until all bridging is installed and anchored.

1926.757(d)(4)

For steel members spanning over 144 feet (43.9 m), the erection methods used shall be in accordance with § 1926.756.

1926.757(d)(5)

Where any steel joist specified in paragraphs (c)(2) and (d)(1), (d)(2), and (d)(3) of this section is a bottom chord bearing joist, a row of bolted diagonal bridging shall be provided near the support(s). This bridging shall be installed and anchored before the hoisting cable(s) is released.

1926.757(d)(6)

When bolted diagonal erection bridging is required by this section, the following shall apply:

1926.757(d)(6)(i)

The bridging shall be indicated on the erection drawing;

1926.757(d)(6)(ii)

The erection drawing shall be the exclusive indicator of the proper placement of this bridging;

OSHA[®] GUIDELINES

PROVIDED BY *Thread Source, Inc.*

1926.757(d)(6)(iii)

Shop-installed bridging clips, or functional equivalents, shall be used where the bridging bolts to the steel joists;

1926.757(d)(6)(iv)

When two pieces of bridging are attached to the steel joist by a common bolt, the nut that secures the first piece of bridging shall not be removed from the bolt for the attachment of the second; and

1926.757(d)(6)(v)

Bridging attachments shall not protrude above the top chord of the steel joist.

1926.757(e)

Landing and placing loads.

..1926.757(e)(1)

1926.757(e)(1)

During the construction period, the employer placing a load on steel joists shall ensure that the load is distributed so as not to exceed the carrying capacity of any steel joist.

1926.757(e)(2)

Except for paragraph (e)(4) of this section, no construction loads are allowed on the steel joists until all bridging is installed and anchored and all joist-bearing ends are attached.

1926.757(e)(3)

The weight of a bundle of joist bridging shall not exceed a total of 1,000 pounds (454 kg). A bundle of joist bridging shall be placed on a minimum of three steel joists that are secured at one end. The edge of the bridging bundle shall be positioned within 1 foot (.30 m) of the secured end.

1926.757(e)(4)

No bundle of decking may be placed on steel joists until all bridging has been installed and anchored and all joist bearing ends attached, unless all of the following conditions are met:

1926.757(e)(4)(i)

The employer has first determined from a qualified person and documented in a site-specific erection plan that the structure or portion of the structure is capable of supporting the load;

1926.757(e)(4)(ii)

The bundle of decking is placed on a minimum of three steel joists;

1926.757(e)(4)(iii)

The joists supporting the bundle of decking are attached at both ends;

1926.757(e)(4)(iv)

At least one row of bridging is installed and anchored;

1926.757(e)(4)(v)

The total weight of the bundle of decking does not exceed 4,000 pounds (1816 kg); and

1926.757(e)(4)(vi)

OSHA[®] GUIDELINES

PROVIDED BY *Thread Source, Inc.*

Placement of the bundle of decking shall be in accordance with paragraph (e)(5) of this section.

1926.757(e)(5)

The edge of the construction load shall be placed within 1 foot (.30 m) of the bearing surface of the joist end.

[66 FR 5270, Jan. 18, 2001]